

**OBIECTIV:** Reparatie bucla intoarcere tramvai George Enescu (capat 102)  
**OBIECTUL:** REABILITARE CALE DE RULARE TRAMVAI  
**ANTEMASURATO** DEMONTARE LINII DE TRAMVAI  
**ARE:**  
**Beneficiar:** ELTRANS SA  
**Proiectant:** TOTAL PROIECT SRL



AutORIZATIE AFER seria AF nr. 4067/2011

Agrement tehnic seria AT nr. 017/2011

**S.C. TOTAL PROIECT S.R.L. IASI**

**Proiect:** Reparatie bucla intoarcere tramvai George Enescu (capat 102) **nr: 14**

Data: 11.04.2014

**Antemasuratoare  
lista cu cantitati de lucrari fara preturi**

Nr.	Simbol	Denumire	UM	Cantitate
0	1	2	3	4
	DG05A1	Decaparea de imbracaminti cu stratul pana la 3 cm grosime, formate din : covoare asfaltice permanente,betoane asfaltice	mp	1,190.00
			Ore	642.60
Grosime straturi asfalt 9 cm 132*3*3 +1,188.00			=	
			= 1188	
			ROT = 1190	
	L2B02B11	Cai in aliament ...sa canal pe traverse sa semibuna ecartament normal si gust - demontare -	km	0.13
			Ore	320.48
132/1000			= +0.13	
			= .13	
			ROT = 0.132	
	L2C07A1	Taierea sinelor...cu flacara	buc	44.00
			Ore	9.90
			Greutate	0.02
132/6*2			= +44.00	
			= 44	
			ROT = 44	
	TRA02A10	Transportul rutier al materialelor,semifabricatelor cu autocamionul pe dist.= ...10 km.	tona	85.60
132*3*2.4*9/1000			= +85.54	
			= 85.54	
			ROT = 85.6	
	2435	Dispozitiv pt. taierea placilor	ora	8.00

**Note:**

Proiectant  
ing. Ivascan Gabriel



0

1

2

3

4

