

OBIECTIV: Reparatie bucla intoarcere tramvai George Enescu (capat 102)
OBIECTUL: REABILITARE CALE DE RULARE TRAMVAI
ANTEMASURATO SUPRASTRUCTURA LINIE TRAMVAI
ARE:
Beneficiar: ELTRANS SA
Proiectant: TOTAL PROIECT SRL



AutORIZATIE AFER seria AF nr. 4067/2011

Agrement tehnic seria AT nr. 017/2011

S.C. TOTAL PROIECT S.R.L. IASI

Proiect: Reparatie bucla intoarcere tramvai George Enescu (capat 102) **nr: 14**

Data: 11.04.2014

**Antemasuratoare
lista cu cantitati de lucrari fara preturi**

Nr.	Simbol	Denumire	UM	Cantitate
0	1	2	3	4
	L1C16A1	Confectionarea cupoanelor de racordare prin sudare electrica dupa procesul topirii intermediare si presiunii,...cu instalatia mobila diesel-electrica de sudare a sinelor	buc	4.00
			Ore	56.00
			Greutate	0.28
	L1D14A1	Inlocuirea sinelor de cale ferata normala...tip 65	m	8.00
			Ore	4.78
			Greutate	0.52
	L2B61A1	Curbarea sau indreptarea sinelor ...a mot. generat.	m	106.00
			Ore	74.73
	L2C01B1	Sudare elect. sinelor cap la cap placi later. si sub tabla sinei sina...canal semibuna nemontata cale	buc	44.00
			Ore	366.74
			Greutate	1.00
132*2/6				= +44.00
=====				= 44
				ROT = 44
	L2B04A1	Poza caii in curba cu sina cu canal...sina noua 64,8kg/m ecartament normal	km	0.13
			Ore	887.55
			Greutate	18.86
	2958768	Traversa fag normale neimp. cl I G = 15x25cm L = 2,60m	buc	212.00
			Greutate	21.20

Note:

Proiectant
ing. Ivascan Gabriel

